

Notes

- 1. All works shall be carried out in accordance with the Contract Specification and the Manual of Contract Documents for Highway Works including revision/amendments and any Client specific additional or substitute clauses.
- 2. The Contractor shall determine the location and status of any statutory utility apparatus prior to the commencement of any works.

Key


- Proposed kerb line
- Proposed tactile paving
- Proposed road markings

Scope


- Scope of proposed works will include following:
- 1. Construction of new dedicated filter lane and shared use footway from Holloway Head to Suffolk St Queensway
  - 2. Installation of traffic signals to improve traffic flow at the roundabout
  - 3. Upgrade of existing street lighting to LED standard and illumination of central island
  - 4. Upgrade of 2 existing Pelican crossing to Toucan
  - 5. Resurfacing of the roundabout
  - 6. Modifications to road markings
  - 7. Modifications to signs
  - 8. Relocation of existing digital signature sign
  - 9. Relocation of existing CCTV camera to the central island
  - 10. Maintenance works for the subways - subject to agreement with Arney PFI
  - 11. Installation of new CCTV cameras at the central island and potentially in the subways

FILE PATH: \\XACAD\project\Commissioning\CA-02581\Holloway\Drawings\CA-02581\_S1\_001 Rev-GA Callout Brief.dwg

A1



ANNE SHAW  
ASSISTANT DIRECTOR  
TRANSPORTATION AND CONNECTIVITY  
1 LANCASTER CIRCUS  
BIRMINGHAM B4 7DG



This map is based upon Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office Crown copyright. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings. B.C.C. Licence No 100021326 Date 2017

SCHEME		HOLLOWAY CIRCUS PINCH POINT SCHEME			
DRAWING		GENERAL ARRANGEMENT			
DRAWN	REV.	DESIGNER	PM	REVISIONS	DRN/PM
KS	14/07/17	NT	NT	14/07/17	-
DRAWING STATUS		SCALE			
GENERAL		1:500			
DWG. No		CA-02581 S1_001			